

BID
REVISED 5/4/2017

TO THE CITY OF ROME, GEORGIA

Submitted: _____, 2017

The undersigned, as Bidder, hereby declares that the only person or persons interested in the Bid as principal or principals is or are named herein and that no other person than herein mentioned has any interest in this Bid or in the Contract to be entered into; that this Bid is made without connection with any other person, company or parties making bid or Bid; and that it is in all respects fair and in good faith without collusion or fraud.

The Bidder further declares that he has examined all Drawings and the Specifications for the work and has read all Instructions to Bidders and General Conditions furnished prior to the opening of bids; that he has satisfied himself relative to the work to be performed.

The Bidder proposes and agrees, if this Bid is accepted, to contract with the City of Rome, Georgia, in the form of contract specified, to furnish all necessary products, machinery, tools, apparatus, means of transportation and labor necessary to complete the construction of **EAST ROME – EAST 12TH SIDEWALK IMPROVEMENTS – PHASE 1, Bid No. 023-17**, in full and complete accordance with the noted, and reasonably intended requirements of the Specifications and Contract Documents to the full and entire satisfaction of the City with a definite understanding that no money will be allowed for extra work except as set forth in the attached General Conditions and Contract Documents, for the following prices:

B-1

(DO NOT DETACH)

(CONTRACT "A")

Contract "A" shall consist of the removal and replacement of existing concrete curb and gutter, concrete sidewalks and drives (including drive aprons) along the south side of East 12th Street, SW, from the intersection of East 12th Street, SW, and Maple Street, SW, westerly to the intersection of East 12th Street, SW and Crane Street, SW as well as said intersection. All concrete curb and gutter installed shall be adjusted from its current elevation to match the existing pavement. This contract shall also include drainage improvements at said intersection in addition to the items listed above. The approximate footage for this contract is 550 linear feet.

ITEM 1A – For furnishing all materials and performing all labor necessary to complete EAST ROME – EAST 12TH SIDEWALK IMPROVEMENTS – PHASE 1, including all work shown and/or specified and **NOT** included in Items 2A through 12A below, the amount of

_____ Dollars (\$_____).

ITEM 2A – 30-INCH CURB AND GUTTER (REMOVE & REPLACE)

a. 460 LF (GDOT 9032B) \$_____ /LF \$_____

ITEM 3A – SIDEWALK (REMOVE & REPLACE)

a. 325 SY 4"-Thick \$_____ /SY \$_____

Including curb cut (Wheelchair) ramps, old and new

ITEM 4A – DETECTABLE WARNING SURFACE WITHIN WHEEL CHAIR RAMP

a. 3 EA Matt Type \$_____ /EA \$_____

ITEM 5A – CONCRETE DRIVES – ROME STANDARD (REMOVE & REPLACE)

a. 120 LF 6" Driveway Concrete \$_____ /LF \$_____

With 6" compacted G.A.B.

ITEM 6A – DRIVEWAY CONCRETE (REMOVE & REPLACE)

B-2

(DO NOT DETACH)

a. 70 SY 6" Thick Concrete \$_____ /SY \$_____
With 6" compacted G.A.B.

ITEM 7A – GDOT TYPE 1033D CATCH BASIN

a. 1 EA (0' – 6") \$_____ /EA \$_____
With Lt. Duty Ring & Cover

ITEM 8A – GDOT TYPE 1019A TYPE "E" DROP INLET

a. 2 EA (0' – 6") \$_____ /EA \$_____
EJIW 7510 with M3 Grate

ITEM 9A – 18" STORM DRAIN PIPE

a. 55 LF (0' – 6") \$_____ /LF \$_____
Under Roadway

ITEM 10A – REMOVE EXISTING DROP INLETS AND SEAL PIPES

a. 2 EA (0' – 6") \$_____ /EA \$_____
Existing Iron Work to be returned to City of Rome

ITEM 11A – ADJUST EXIST. J.B. TO GRADE

a. 1 EA (0' – 6") \$_____ /EA \$_____
With new Lt. Duty Ring and Cover

ITEM 12A – GRADE AND COMPACT AREA BETWEEN OLD & NEW CURB LINE

a. 30 SY (0' – 6") \$_____ /SY \$_____
Compact subgrade, provide compacted
10-inches GAB left down for 2-inches
paving by City of Rome

SUB-TOTAL ITEMS 1A THROUGH 12A, INCLUSIVE IN THE AMOUNT OF

DOLLARS
(\$_____).

(CONTRACT "B")

Contract "B" shall consist of the removal and replacement of existing concrete curb and gutter, sidewalks and drives (including drive aprons which will be replaced with 30-inch concrete curb and gutter and a 3-ft. grass strip) along the south side of Maple Street, SW, from the west side of Crane Street, SW, in a westerly direction to the radius return on Cedar Avenue, SW at the intersection of Maple Street, SW, and Cedar Avenue, SW. All concrete curb and gutter installed shall be adjusted from its current elevation to match the existing pavement. This contract shall also include drainage improvements on the south side of Maple Street, SW, on the south side of Maple Street, SW at the intersection of Maple Street, SW, and Walnut Avenue, SW. Approximate footage for this contract is 675 linear feet.

ITEM 1B – For furnishing all materials and performing all labor necessary to complete EAST ROME – EAST 12TH SIDEWALK IMPROVEMENTS – PHASE 1, including all work shown and/or specified and **NOT** included in Items 2B through 9B below, the amount of

_____ Dollars (\$_____).

ITEM 2B – 30-INCH CURB AND GUTTER (REMOVE & REPLACE)

a. 400 LF Rome Standard \$_____ /LF \$_____

ITEM 3B – SIDEWALK (REMOVE & REPLACE)

a. 400 SY 4"-Thick \$_____ /SY \$_____

Including curb cut (Wheelchair) ramps, old and new

ITEM 4B – DETECTABLE WARNING SURFACE WITHIN WHEEL CHAIR RAMP

a. 1 EA Matt Type \$_____ /EA \$_____

ITEM 5B – CONCRETE DRIVES – (REMOVE & REPLACE W/30" CURB AND GUTTER,
3-FT. GRASS STRIP WITH TOP SOIL, SEEDED AND MULCHED W/HAY)

a. 325 LF 30" Curb and Gutter \$ _____/LF \$ _____
With 3-ft. grass strip, top soil, seeded and mulched w/hay)

ITEM 6B – CONVERT EXISTING DROP INLET TO GDOT TYPE 1034D CATCH BASIN

a. 1 EA 0'-6 \$ _____/EA \$ _____
Return Hood and Grate to City of Rome

ITEM 7B – CONVERT EXISTING DROP INLET TO GDOT TYPE 1033D CATCH BASIN

a. 1 EA 0'-6 \$ _____/EA \$ _____
Return Hood and Grate to City of Rome

ITEM 8B – GDOT TYPE 1019-A TYPE “B”DROP INLET

a. 1 EA 0'-6 \$ _____/EA \$ _____
With Lt. Duty Ring & Cover

ITEM 9B – MODIFY EXIST. JB. TO ADJUST TO GRADE AND ADD 1019-A DROP INLET

a. 1 EA 0'-6 \$ _____/EA \$ _____
Exiting lid 8'x6', New lid to have Lt. Duty Ring& Cover

SUB-TOTAL ITEMS 1B THROUGH 9B, INCLUSIVE IN THE AMOUNT OF

DOLLARS
(\$ _____).

(CONTRACT "C")

Contract "C" shall consist of the removal and replacement of existing concrete curb and gutter, sidewalks and drives (including drive aprons, drive along Cedar between East 12th Street, SW, and East 13th Street, SW, will be replaced with 30-inch curb and gutter and 5-ft. concrete sidewalk abutting said curb, no drive(s) to be replaced) along the east side of Cedar Avenue, SW, beginning at the radius return on Cedar Avenue at the intersection of Maple Street, SW, and Cedar Avenue, SW, in a southerly direction along the east side of Cedar Avenue, SW to the intersection of Cedar Avenue, SW, and East 13th Street, SW, as well as the said intersection. All concrete curb and gutter installed shall be adjusted from its current elevation to match the existing pavement. This contract shall also include drainage improvements at the intersection of Cedar Avenue, SW, and East 13th Street, SW. Also included is removal and replacement of sidewalk at an isolated location on East 13th Street, SW, just west of the round-a-bout, and removal and replacement of concrete curb and gutter, sidewalk and drive (including drive apron) located between 1305 and 1309 Cedar Avenue, SW, and a drive between 1339 and 1341 Cedar Avenue, SW. Approximate footage for this contract is 500 linear feet.

ITEM 1C – For furnishing all materials and performing all labor necessary to complete EAST ROME – EAST 12TH SIDEWALK IMPROVEMENTS – PHASE 1, including all work shown and/or specified and **NOT** included in Items 2C through 9C below, the amount of

_____ Dollars (\$_____).

ITEM 2C – 30-INCH CURB AND GUTTER (REMOVE & REPLACE)

a. 225 LF Rome Standard \$_____ /LF \$_____

ITEM 3C – SIDEWALK (REMOVE & REPLACE)

a. 275 SY 4"-Thick \$_____ /SY \$_____

Including curb cut (Wheelchair) ramps, old and new

ITEM 4C – DETECTABLE WARNING SURFACE WITHIN WHEEL CHAIR RAMP

a. 6 EA Matt Type \$_____ /EA \$_____

ITEM 5C – CONCRETE DRIVES – ROME STANDARD (REMOVE & REPLACE WITH 30-INCH CURB AND GUTTER)

a. 150 LF 6" Driveway Concrete \$ _____/LF \$ _____
To be Replaced with 30-inch Curb & Gutter

ITEM 6C – CONCRETE DRIVES – ROME STANDARD (REMOVE & REPLACE)

a. 45 LF 6" Driveway Concrete \$ _____/LF \$ _____
With 6" compacted G.A.B.

ITEM 7C – DRIVEWAY CONCRETE (REMOVE & REPLACE)

a. 10 SY 6" Thick Concrete \$ _____/SY \$ _____
With 6" compacted G.A.B.

ITEM 8C – CONVERT EXISTING DROP INLET TO GDOT TYPE 1034D CATCH BASIN

a. 1 EA 0'-6" \$ _____/EA \$ _____
Return Hood and Grate to City of Rome

ITEM 9C – MODIFY EXITING DROP INLET ON SOUTH SIDE OF EAST 13th

a. 1 EA 0'-6" \$ _____/EA \$ _____
Lower Frame and Grate by Approx. 2-inches to
insure positive drainage to inlet.

SUB-TOTAL ITEMS 1C THROUGH 9C, INCLUSIVE IN THE AMOUNT OF
_____ DOLLARS
(\$ _____).

GRAND TOTAL CONTRACTS "A" THROUGH "C", INCLUSIVE IN THE AMOUNT OF

DOLLARS
(\$_____).

The Bidder agrees hereby to commence work under this Contract, with adequate personnel and equipment, on a date to be specified in a written order of the Owner, and to fully complete all work under this Contract as determined by the Owner and Bidder.

The Bidder declares that he understands that quantities for unit price items are minimums and are subject to increase, and that should the quantities of any of the items of work be increased, the Bidder proposes to do the additional work at the unit prices stated herein.

Bidder acknowledges receipt of Addenda _____.

Bidder: _____

By: _____

Title: _____

Address: _____

Phone: _____

Attached hereto is a Bid Bond for the sum of _____ Dollars
(\$_____) according to the conditions of "Instructions to Bidders" and provisions thereof.

The full names and addresses of persons or parties interested in the foregoing bid, as principals, are as follows:

The Bidder lists below work he has done of similar nature to that bid for, as references that will afford the Owner opportunity to judge as to experience, skill, business standing, and financial ability.